



WorkStation Industries

Base Cabinet Construction and Specifications

- 100% 18ga Solid steel welded construction
- 4" Toe Kick
- xx"W x 22"D x 35"H
- Removable back panel
- Levelers come with 12ga gusset leveling plate
- Glides are zinc and 100% zinc plated and are adjustable inside cabinet
- Welded front stringer beam keeps cabinet square and able to support 300lb load bearing
- Powder coating 600 hour positive salt tested
- 1 year limited warranty

Cabinet Drawers Construction and Specifications

- 100lb ball bearing drawers slide extensions
- Double wall face parts
- 18" 100lb Drawer full pull extension
- 5" Aluminum handle pulls
- Drawer bottoms are full formed
- Side mounting brackets welded to outside drawer
- Detachable face drawer
- Lab cabinet meets and has been approved by SEFA requirements
- Powder coating 600 hour positive salt tested
- 1 year limited warranty